



# Transitioning from MetroCluster FC to MetroCluster IP configurations

ONTAP MetroCluster

NetApp  
September 12, 2021

This PDF was generated from [https://docs.netapp.com/us-en/ontap-metrocluster/transition/task\\_verify\\_mcc\\_health\\_fc\\_to\\_ip.html](https://docs.netapp.com/us-en/ontap-metrocluster/transition/task_verify_mcc_health_fc_to_ip.html) on September 12, 2021. Always check docs.netapp.com for the latest.

# Table of Contents

- Transitioning from MetroCluster FC to MetroCluster IP configurations ..... 1
  - Verifying the health of the MetroCluster configuration ..... 1
  - Removing the existing configuration from the Tiebreaker or other monitoring software ..... 4
  - Generating and applying RCFs to the new IP switches ..... 4
  - Moving the local cluster connections ..... 5
  - Preparing the MetroCluster IP controllers ..... 16
  - Configure the MetroCluster for transition ..... 17
  - Moving the data to the new drive shelves ..... 36
  - Removing the MetroCluster FC controllers ..... 37
  - Completing the transition ..... 44

# Transitioning from MetroCluster FC to MetroCluster IP configurations

After reviewing all requirements and preparing for the transition, you perform the transition procedure. You must perform each task in order, completing all steps in each task before moving to the next. You should not connect the new controllers or storage shelves to the existing configuration until directed.

## Verifying the health of the MetroCluster configuration

You must verify the health and connectivity of the MetroCluster configuration prior to performing the transition

1. Verify the operation of the MetroCluster configuration in ONTAP:
  - a. Check whether the system is multipathed: `node run -node node-name sysconfig -a`
  - b. Check for any health alerts on both clusters: `system health alert show`
  - c. Confirm the MetroCluster configuration and that the operational mode is normal: `metrocluster show`
  - d. Perform a MetroCluster check: `metrocluster check run`
  - e. Display the results of the MetroCluster check: `metrocluster check show`
  - f. Check for any health alerts on the switches (if present): `storage switch show`
  - g. Run Config Advisor.

[NetApp Downloads: Config Advisor](#)

- h. After running Config Advisor, review the tool's output and follow the recommendations in the output to address any issues discovered.
2. Verify that the cluster is healthy: `cluster show`

```
cluster_A::> cluster show
Node           Health  Eligibility  Epsilon
-----
node_A_1_FC    true   true         false
node_A_2_FC    true   true         false

cluster_A::>
```

3. Verify that all cluster ports are up: `network port show -ipspace cluster`

```
cluster_A::> network port show -ipspace cluster
```

```
Node: node_A_1_FC
```

Port	IPspace	Broadcast	Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster		up	9000	auto/10000	healthy
e0b	Cluster	Cluster		up	9000	auto/10000	healthy

```
Node: node_A_2_FC
```

Port	IPspace	Broadcast	Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster		up	9000	auto/10000	healthy
e0b	Cluster	Cluster		up	9000	auto/10000	healthy

```
4 entries were displayed.
```

```
cluster_A::>
```

4. Verify that all cluster LIFs are up and operational: `network interface show -vserver cluster`

Each cluster LIF should display "true" for "Is Home" and "up/up" for "Status Admin/Oper".

```
cluster_A::> network interface show -vserver cluster
```

Current Is	Logical	Status	Network	Current	
Vserver	Interface	Admin/Oper	Address/Mask	Node	Port
Home					
-----	-----	-----	-----	-----	-----
Cluster					
true	node_A-1_FC_clus1	up/up	169.254.209.69/16	node_A-1_FC	e0a
true	node_A_1_FC_clus2	up/up	169.254.49.125/16	node_A_1_FC	e0b
true	node_A_2_FC_clus1	up/up	169.254.47.194/16	node_A_2_FC	e0a
true	node_A_2_FC_clus2	up/up	169.254.19.183/16	node_A_2_FC	e0b

```
4 entries were displayed.
```

```
cluster_A::>
```

5. Verify that auto-revert is enabled on all cluster LIFs: `network interface show -vserver Cluster -fields auto-revert`

```

cluster_A::> network interface show -vserver Cluster -fields auto-revert

          Logical
Vserver  Interface      Auto-revert
-----  -
Cluster
          node_A_1_FC_clus1
                        true
          node_A_1_FC_clus2
                        true
          node_A_2_FC_clus1
                        true
          node_A_2_FC_clus2
                        true

          4 entries were displayed.

cluster_A::>

```

## Removing the existing configuration from the Tiebreaker or other monitoring software

If the existing configuration is monitored with the MetroCluster Tiebreaker configuration or other third-party applications (for example, ClusterLion) that can initiate a switchover, you must remove the MetroCluster configuration from the Tiebreaker or other software prior to transition.

1. Remove the existing MetroCluster configuration from the Tiebreaker software.

[Removing MetroCluster configurations](#)

2. Remove the existing MetroCluster configuration from any third-party application that can initiate switchover.

Refer to the documentation for the application.

## Generating and applying RCFs to the new IP switches

If you are using new IP switches for the MetroCluster IP configuration, you must configure the switches with a custom RCF file.

This task is required if you are using new switches.

If you are using existing switches, proceed to [Moving the local cluster connections](#).

1. Install and rack the new IP switches.

2. Prepare the IP switches for the application of the new RCF files.

Follow the steps in the section for your switch vendor from the [MetroCluster IP Installation and Configuration Guide](#)

- [Resetting the Broadcom IP switch to factory defaults](#)
- [Resetting the Cisco IP switch to factory defaults](#)

3. Update the firmware on the switch to a supported version, if necessary.

4. Use the RCF generator tool to create the RCF file depending on your switch vendor and the platform models, and then update the switches with the file.

Follow the steps in the section for your switch vendor from the *MetroCluster IP Installation and Configuration guide*.

[MetroCluster IP installation and configuration](#)

- [Downloading and installing the Broadcom IP RCF files](#)
- [Downloading and installing the Cisco IP RCF files](#)

## Moving the local cluster connections

You must move the MetroCluster FC configuration's cluster interfaces to the IP switches.

### Moving the cluster connections on the MetroCluster FC nodes

You must move the cluster connections on the MetroCluster FC nodes to the IP switches. The steps depend on whether you are using the existing IP switches or you are using new IP switches.

You must perform this task on both MetroCluster sites.

The following task assumes a controller module using two ports for the cluster connections. Some controller module models use four or more ports for the cluster connection. In that case, for the purposes of this example, the ports are divided into two groups, alternating ports between the two groups

The following table shows the example ports used in this task.

Number of cluster connections on the controller module	Group A ports	Group B ports
Two	e0a	e0b
Four	e0a, e0c	e0b, e0d

- Group A ports connect to local switch switch\_x\_1-IP.
- Group B ports connect to local switch switch\_x\_2-IP.

The following table shows which switch ports the FC nodes connect to. For the Broadcom BES-53248 switch, the port usage depends on the model of the MetroCluster IP nodes.

Switch model	MetroCluster IP node model	Switch port(s)	Connects to
Cisco 3132Q-V or 3232C	Any	5	node_x_1-FC
		6	node_x_2-FC
Broadcom BES-53248	FAS2750/A220	1, 2, 3	node_x_1-FC
	FAS8200 / A300	1, 2, 3, 7, 8, 9	node_x_1-FC
	FAS2750/A220	4, 5, 6	node_x_2-FC
	FAS8200 / A300	4, 5, 6, 10, 11, 12	node_x_2-FC

### Moving the local cluster connections when using new IP switches

If you are using new IP switches, you must physically move the existing MetroCluster FC nodes' cluster connections to the new switches.

1. Move the MetroCluster FC node group A cluster connections to the new IP switches.

Use the ports described in [Moving the cluster connections on the MetroCluster FC nodes](#).

- a. Disconnect all the group A ports from the switch, or, if the MetroCluster FC configuration was a switchless cluster, disconnect them from the partner node.
  - b. Disconnect the group A ports from node\_A\_1-FC and node\_A\_2-FC.
  - c. Connect the group A ports of node\_A\_1-FC to the switch ports for the FC node on switch\_A\_1-IP
  - d. Connect the group A ports of node\_A\_2-FC to the switch ports for the FC node on switch\_A\_1-IP
2. Verify that all cluster ports are up: `network port show -ip space Cluster`



```
cluster_A::*> network port show -ipSpace Cluster
```

```
Node: node_A_1-FC
```

Port	IPspace	Broadcast	Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster		up	9000	auto/10000	healthy
e0b	Cluster	Cluster		up	9000	auto/10000	healthy

```
Node: node_A_2-FC
```

Port	IPspace	Broadcast	Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster		up	9000	auto/10000	healthy
e0b	Cluster	Cluster		up	9000	auto/10000	healthy

```
4 entries were displayed.
```

```
cluster_A::*>
```

3. Verify that all interfaces display true in the Is Home column: `network interface show -vserver cluster`

This might take several minutes to complete.

```

cluster_A::*> network interface show -vserver cluster

          Logical      Status      Network      Current
Current Is
Vserver   Interface  Admin/Oper  Address/Mask  Node      Port
Home
-----
-----
Cluster
          node_A_1_FC_clus1
          up/up      169.254.209.69/16  node_A_1_FC  e0a
true
          node_A_1-FC_clus2
          up/up      169.254.49.125/16  node_A_1-FC  e0b
true
          node_A_2-FC_clus1
          up/up      169.254.47.194/16  node_A_2-FC  e0a
true
          node_A_2-FC_clus2
          up/up      169.254.19.183/16  node_A_2-FC  e0b
true

4 entries were displayed.

cluster_A::*>

```

4. Perform the above steps on both nodes (node\_A\_1-FC and node\_A\_2-FC) to move the group B ports of the cluster interfaces.
5. Repeat the above steps on the partner cluster "cluster\_B".

### Moving the local cluster connections when reusing existing IP switches

If you are reusing existing IP switches, you must update firmware, reconfigure the switches with the correct Reference Configure Files (RCFs) and move the connections to the correct ports one switch at a time.

This task is required only if the FC nodes are connected to existing IP switches and you are reusing the switches.

1. Disconnect the local cluster connections that connect to switch\_A\_1\_IP
  - a. Disconnect the group A ports from the existing IP switch.
  - b. Disconnect the ISL ports on switch\_A\_1\_IP.

You can see the Installation and Setup instructions for the platform to see the cluster port usage.

[AFF A320 systems: Installation and setup](#)

[AFF A220/FAS2700 Systems Installation and Setup Instructions](#)

[AFF A800 Systems Installation and Setup Instructions](#)

[AFF A300 Systems Installation and Setup Instructions](#)

[FAS8200 Systems Installation and Setup Instructions](#)

2. Reconfigure switch\_A\_1\_IP using RCF files generated for your platform combination and transition.

Follow the steps in the section for your switch vendor from the *MetroCluster IP Installation and Configuration guide*, as given in the links below.

#### [MetroCluster IP installation and configuration](#)

- a. If required, download and install the new switch firmware.

You should use the latest firmware that the MetroCluster IP nodes support.

- [Downloading and installing the Broadcom switch EFOS software](#)
- [Downloading and installing the Cisco switch NX-OS software](#)

- b. Prepare the IP switches for the application of the new RCF files.

- [Resetting the Broadcom IP switch to factory defaults \\*\\*](#)
- [Resetting the Cisco IP switch to factory defaults](#)

- c. Download and install the IP RCF file depending on your switch vendor.

- [Downloading and installing the Broadcom IP RCF files](#)
- [Downloading and installing the Cisco IP RCF files](#)

3. Reconnect the group A ports to switch\_A\_1\_IP.

Use the ports described in [Moving the cluster connections on the MetroCluster FC nodes](#).

4. Verify that all cluster ports are up: `network port show -ip space cluster`

```
Cluster-A::*> network port show -ipSpace cluster
```

```
Node: node_A_1_FC
```

Port	IPspace	Broadcast Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster	up	9000	auto/10000	healthy
e0b	Cluster	Cluster	up	9000	auto/10000	healthy

```
Node: node_A_2_FC
```

Port	IPspace	Broadcast Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster	up	9000	auto/10000	healthy
e0b	Cluster	Cluster	up	9000	auto/10000	healthy

```
4 entries were displayed.
```

```
Cluster-A::*>
```

5. Verify that all interfaces are on their home port: `network interface show -vserver Cluster`

```

Cluster-A::*> network interface show -vserver Cluster

Current Is
Vserver    Logical      Status      Network      Current
Home       Interface   Admin/Oper  Address/Mask  Node         Port
-----
Cluster
node_A_1_FC_clus1
              up/up      169.254.209.69/16  node_A_1_FC  e0a
true
node_A_1_FC_clus2
              up/up      169.254.49.125/16  node_A_1_FC  e0b
true
node_A_2_FC_clus1
              up/up      169.254.47.194/16  node_A_2_FC  e0a
true
node_A_2_FC_clus2
              up/up      169.254.19.183/16  node_A_2_FC  e0b
true

4 entries were displayed.

Cluster-A::*>

```

6. Repeat all the previous steps on switch\_A\_2\_IP.
7. Reconnect the local cluster ISL ports.
8. Repeat the above steps at site\_B for switch B\_1\_IP and switch B\_2\_IP.
9. Connect the remote ISLs between the sites.

## Verifying that the cluster connections are moved and the cluster is healthy

To ensure that there is proper connectivity and that the configuration is ready to proceed with the transition process, you must verify that the cluster connections are moved correctly, the cluster switches are recognized and the cluster is healthy.

1. Verify that all cluster ports are up and running: `network port show -ipSPACE Cluster`

```
Cluster-A::*> network port show -ipspace Cluster
```

```
Node: Node-A-1-FC
```

Port	IPspace	Broadcast	Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster		up	9000	auto/10000	healthy
e0b	Cluster	Cluster		up	9000	auto/10000	healthy

```
Node: Node-A-2-FC
```

Port	IPspace	Broadcast	Domain	Link	MTU	Speed(Mbps) Admin/Oper	Health Status
e0a	Cluster	Cluster		up	9000	auto/10000	healthy
e0b	Cluster	Cluster		up	9000	auto/10000	healthy

```
4 entries were displayed.
```

```
Cluster-A::*>
```

2. Verify that all interfaces are on their home port: `network interface show -vserver Cluster`

This might take several minutes to complete.

The following example shows that all interfaces show true in the Is Home column.

```
Cluster-A::*> network interface show -vserver Cluster
```

Current Is	Logical	Status	Network	Current	
Vserver	Interface	Admin/Oper	Address/Mask	Node	Port
Home					
-----	-----	-----	-----	-----	-----
Cluster					
true	Node-A-1_FC_clus1	up/up	169.254.209.69/16	Node-A-1_FC	e0a
true	Node-A-1-FC_clus2	up/up	169.254.49.125/16	Node-A-1-FC	e0b
true	Node-A-2-FC_clus1	up/up	169.254.47.194/16	Node-A-2-FC	e0a
true	Node-A-2-FC_clus2	up/up	169.254.19.183/16	Node-A-2-FC	e0b

```
4 entries were displayed.
```

```
Cluster-A::*>
```

3. Verify that both the local IP switches are discovered by the nodes: `network device-discovery show -protocol cdp`

```
Cluster-A::*> network device-discovery show -protocol cdp
```

Node/ Protocol	Local Port	Discovered Device (LLDP: ChassisID)	Interface	Platform
-----				
Node-A-1-FC				
	/cdp			
	e0a	Switch-A-3-IP	1/5/1	N3K-
C3232C				
	e0b	Switch-A-4-IP	0/5/1	N3K-
C3232C				
Node-A-2-FC				
	/cdp			
	e0a	Switch-A-3-IP	1/6/1	N3K-
C3232C				
	e0b	Switch-A-4-IP	0/6/1	N3K-
C3232C				

```
4 entries were displayed.
```

```
Cluster-A::*>
```

4. On the IP switch, verify that the MetroCluster IP nodes have been discovered by both local IP switches:  
show cdp neighbors

You must perform this step on each switch.

This example shows how to verify the nodes are discovered on Switch-A-3-IP.



```
(Switch-A-3-IP)# show cdp neighbors
```

```
Capability Codes: R - Router, T - Trans-Bridge, B - Source-Route-Bridge  
S - Switch, H - Host, I - IGMP, r - Repeater,  
V - VoIP-Phone, D - Remotely-Managed-Device,  
s - Supports-STP-Dispute
```

Device-ID ID	Local Intrfce	Hldtme	Capability	Platform	Port
Node-A-1-FC	Eth1/5/1	133	H	FAS8200	e0a
Node-A-2-FC	Eth1/6/1	133	H	FAS8200	e0a
Switch-A-4-IP (FDO220329A4)	Eth1/7	175	R S I s	N3K-C3232C	Eth1/7
Switch-A-4-IP (FDO220329A4)	Eth1/8	175	R S I s	N3K-C3232C	Eth1/8
Switch-B-3-IP (FDO220329B3)	Eth1/20	173	R S I s	N3K-C3232C	
Eth1/20					
Switch-B-3-IP (FDO220329B3)	Eth1/21	173	R S I s	N3K-C3232C	
Eth1/21					

```
Total entries displayed: 4
```

```
(Switch-A-3-IP)#
```

This example shows how to verify that the nodes are discovered on Switch-A-4-IP.

```
(Switch-A-4-IP)# show cdp neighbors
```

```
Capability Codes: R - Router, T - Trans-Bridge, B - Source-Route-Bridge  
S - Switch, H - Host, I - IGMP, r - Repeater,  
V - VoIP-Phone, D - Remotely-Managed-Device,  
s - Supports-STP-Dispute
```

Device-ID ID	Local Intrfce	Hldtme	Capability	Platform	Port
Node-A-1-FC	Eth1/5/1	133	H	FAS8200	e0b
Node-A-2-FC	Eth1/6/1	133	H	FAS8200	e0b
Switch-A-3-IP (FDO220329A3)	Eth1/7	175	R S I s	N3K-C3232C	Eth1/7
Switch-A-3-IP (FDO220329A3)	Eth1/8	175	R S I s	N3K-C3232C	Eth1/8
Switch-B-4-IP (FDO220329B4)	Eth1/20	169	R S I s	N3K-C3232C	
Eth1/20					
Switch-B-4-IP (FDO220329B4)	Eth1/21	169	R S I s	N3K-C3232C	
Eth1/21					

```
Total entries displayed: 4
```

```
(Switch-A-4-IP)#
```

## Preparing the MetroCluster IP controllers

You must prepare the four new MetroCluster IP nodes and install the correct ONTAP version.

This task must be performed on each of the new nodes:

- node\_A\_1-IP
- node\_A\_2-IP
- node\_B\_1-IP
- node\_B\_2-IP

In these steps, you clear the configuration on the nodes and clear the mailbox region on new drives.

1. Rack the new controllers for the MetroCluster IP configuration.

The MetroCluster FC nodes (node\_A\_x-FC and node\_B\_x-FC) remain cabled at this time.

2. Cable the MetroCluster IP nodes to the IP switches as shown in the [Cabling the IP switches](#).

3. Configure the MetroCluster IP nodes using the following sections:
  - a. [Gathering required information](#)
  - b. [Clearing the configuration on a controller module](#)
  - c. [Verifying the ha-config state of components](#)
  - d. [Manually assigning drives for pool 0 \(ONTAP 9.4 and later\)](#)
4. From Maintenance mode, issue the halt command to exit Maintenance mode, and then issue the boot\_ontap command to boot the system and get to cluster setup.

Do not complete the cluster wizard or node wizard at this time.

5. Repeat these steps on the other MetroCluster IP nodes.

## Configure the MetroCluster for transition

To prepare the configuration for transition you add the new nodes to the existing MetroCluster configuration and then move data to the new nodes.

### Sending a custom AutoSupport message prior to maintenance

Before performing the maintenance, you should issue an AutoSupport message to notify NetApp technical support that maintenance is underway. Informing technical support that maintenance is underway prevents them from opening a case on the assumption that a disruption has occurred.

This task must be performed on each MetroCluster site.

1. To prevent automatic support case generation, send an Autosupport message to indicate maintenance is underway.
  - a. Issue the following command:

```
system node autosupport invoke -node * -type all -message MAINT=maintenance-window-in-hours
```

maintenance-window-in-hours specifies the length of the maintenance window, with a maximum of 72 hours. If the maintenance is completed before the time has elapsed, you can invoke an AutoSupport message indicating the end of the maintenance period:

```
system node autosupport invoke -node * -type all -message MAINT=end
```
  - b. Repeat the command on the partner cluster.

### Enabling transition mode and disabling cluster HA

You must enable the MetroCluster transition mode to allow the old and new nodes to operate together in the MetroCluster configuration, and disable cluster HA.

1. Enable transition:
  - a. Change to the advanced privilege level: `set -privilege advanced`
  - b. Enable transition mode: `metrocluster transition enable -transition-mode non-disruptive`



Run this command on one cluster only.

```
cluster_A::*> metrocluster transition enable -transition-mode non-
disruptive

Warning: This command enables the start of a "non-disruptive"
MetroCluster
          FC-to-IP transition. It allows the addition of hardware for
another DR
          group that uses IP fabrics, and the removal of a DR group
that uses FC
          fabrics. Clients will continue to access their data during a
non-disruptive transition.

          Automatic unplanned switchover will also be disabled by this
command.
Do you want to continue? {y|n}: y

cluster_A::*>
```

c. Return to the admin privilege level: `set -privilege admin`

2. Verify that transition is enabled on both the clusters.

```
cluster_A:::> metrocluster transition show-mode
Transition Mode

non-disruptive

cluster_A::*>

cluster_B::*> metrocluster transition show-mode
Transition Mode

non-disruptive

Cluster_B:::>
```

3. Disable cluster HA.



You must run this command on both clusters.

```
cluster_A::*> cluster ha modify -configured false
```

```
Warning: This operation will unconfigure cluster HA. Cluster HA must be  
configured on a two-node cluster to ensure data access availability in  
the event of storage failover.
```

```
Do you want to continue? {y|n}: y
```

```
Notice: HA is disabled.
```

```
cluster_A::*>
```

```
cluster_B::*> cluster ha modify -configured false
```

```
Warning: This operation will unconfigure cluster HA. Cluster HA must be  
configured on a two-node cluster to ensure data access availability in  
the event of storage failover.
```

```
Do you want to continue? {y|n}: y
```

```
Notice: HA is disabled.
```

```
cluster_B::*>
```

#### 4. Verify that cluster HA is disabled.



You must run this command on both clusters.

```
cluster_A::> cluster ha show
```

```
High Availability Configured: false
```

```
Warning: Cluster HA has not been configured. Cluster HA must be configured
```

```
on a two-node cluster to ensure data access availability in the event of storage failover. Use the "cluster ha modify -configured true" command to configure cluster HA.
```

```
cluster_A::>
```

```
cluster_B::> cluster ha show
```

```
High Availability Configured: false
```

```
Warning: Cluster HA has not been configured. Cluster HA must be configured
```

```
on a two-node cluster to ensure data access availability in the event of storage failover. Use the "cluster ha modify -configured true" command to configure cluster HA.
```

```
cluster_B::>
```

## Joining the MetroCluster IP nodes to the clusters

You must add the four new MetroCluster IP nodes to the existing MetroCluster configuration.

You must perform this task on both clusters.

1. Add the MetroCluster IP nodes to the existing MetroCluster configuration.
  - a. Join the first MetroCluster IP node (node\_A\_1-IP) to the existing MetroCluster FC configuration.

```
Welcome to the cluster setup wizard.
```

```
You can enter the following commands at any time:
```

```
"help" or "?" - if you want to have a question clarified,
```

```
"back" - if you want to change previously answered questions, and
```

```
"exit" or "quit" - if you want to quit the cluster setup wizard.
```

```
Any changes you made before quitting will be saved.
```

```
You can return to cluster setup at any time by typing "cluster setup".
```

```
To accept a default or omit a question, do not enter a value.
```

```
This system will send event messages and periodic reports to NetApp
```

Technical

Support. To disable this feature, enter `autosupport modify -support disable` within 24 hours.

Enabling AutoSupport can significantly speed problem determination and

resolution, should a problem occur on your system.

For further information on AutoSupport, see:

<http://support.netapp.com/autosupport/>

Type `yes` to confirm and continue {yes}: `yes`

Enter the node management interface port [e0M]:

Enter the node management interface IP address: `172.17.8.93`

Enter the node management interface netmask: `255.255.254.0`

Enter the node management interface default gateway: `172.17.8.1`

A node management interface on port `e0M` with IP address `172.17.8.93` has been created.

Use your web browser to complete cluster setup by accessing

`https://172.17.8.93`

Otherwise, press `Enter` to complete cluster setup using the command line

interface:

Do you want to create a new cluster or join an existing cluster?

{create, join}:

`join`

Existing cluster interface configuration found:

Port	MTU	IP	Netmask
<code>e0c</code>	<code>9000</code>	<code>169.254.148.217</code>	<code>255.255.0.0</code>
<code>e0d</code>	<code>9000</code>	<code>169.254.144.238</code>	<code>255.255.0.0</code>

Do you want to use this configuration? {yes, no} [yes]: `yes`

`.`  
`.`  
`.`

- b. Join the second MetroCluster IP node (`node_A_2-IP`) to the existing MetroCluster FC configuration.
2. Repeat these steps to join `node_B_1-IP` and `node_B_2-IP` to `cluster_B`.

## Configuring intercluster LIFs, creating the MetroCluster interfaces, and mirroring root aggregates

You must create cluster peering LIFs, create the MetroCluster interfaces on the new MetroCluster IP nodes.

The home port used in the examples are platform-specific. You should use the appropriate home port specific to MetroCluster IP node platform.

1. On the new MetroCluster IP nodes, [configure the intercluster LIFs](#).
2. On each site, verify that cluster peering is configured: `cluster peer show`

The following example shows the cluster peering configuration on cluster\_A:

```
cluster_A:> cluster peer show
Peer Cluster Name          Cluster Serial Number Availability
Authentication
-----
cluster_B                  1-80-000011      Available      ok
```

The following example shows the cluster peering configuration on cluster\_B:

```
cluster_B:> cluster peer show
Peer Cluster Name          Cluster Serial Number Availability
Authentication
-----
cluster_A 1-80-000011      Available      ok
```

3. Configure the DR group for the MetroCluster IP nodes: `metrocluster configuration-settings dr-group create -partner-cluster`

```
cluster_A::> metrocluster configuration-settings dr-group create
-partner-cluster
cluster_B -local-node node_A_3-IP -remote-node node_B_3-IP
[Job 259] Job succeeded: DR Group Create is successful.
cluster_A::>
```

4. Verify that the DR group is created. `metrocluster configuration-settings dr-group show`



```

cluster_A::> metrocluster configuration-settings dr-group show

DR Group ID Cluster                               Node                               DR Partner
Node
-----
2           cluster_A
           node_A_3-IP                       node_B_3-IP
           node_A_4-IP                       node_B_4-IP
           cluster_B
           node_B_3-IP                       node_A_3-IP
           node_B_4-IP                       node_A_4-IP

4 entries were displayed.

cluster_A::>

```

You will notice that the DR group for the old MetroCluster FC nodes (DR Group 1) is not listed when you run the `metrocluster configuration-settings dr-group show` command.

You can use `metrocluster node show` command on both sites to list all nodes.

```
cluster_A::> metrocluster node show
```

DR	Configuration	DR			
Group	Cluster	Node	State	Mirroring	Mode
1	cluster_A	node_A_1-FC	configured	enabled	normal
		node_A_2-FC	configured	enabled	normal
	cluster_B	node_B_1-FC	configured	enabled	normal
		node_B_2-FC	configured	enabled	normal
2	cluster_A	node_A_1-IP	ready to configure	-	-
		node_A_2-IP	ready to configure	-	-

```
cluster_B::> metrocluster node show
```

DR	Configuration	DR			
Group	Cluster	Node	State	Mirroring	Mode
1	cluster_B	node_B_1-FC	configured	enabled	normal
		node_B_2-FC	configured	enabled	normal
	cluster_A	node_A_1-FC	configured	enabled	normal
		node_A_2-FC	configured	enabled	normal
2	cluster_B	node_B_1-IP	ready to configure	-	-
		node_B_2-IP	ready to configure	-	-

5. Configure the MetroCluster IP interfaces for the newly joined MetroCluster IP nodes: `metrocluster configuration-settings interface create -cluster-name`

See [Configuring and connecting the MetroCluster IP interfaces](#) for considerations when configuring the IP interfaces. NOTE: You can configure the MetroCluster IP interfaces from either cluster. Also, starting with ONTAP 9.9.1, if you are using a layer 3 configuration, you must also specify the `-gateway` parameter when creating MetroCluster IP interfaces. Refer to [xref:./transition/./install-ip/concept\\_considerations\\_layer\\_3.html](#).

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_A -home-node node_A_3-IP -home-port elb -address
172.17.26.10 -netmask 255.255.255.0
[Job 260] Job succeeded: Interface Create is successful.
```

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_A -home-node node_A_3-IP -home-port elb -address
172.17.27.10 -netmask 255.255.255.0
[Job 261] Job succeeded: Interface Create is successful.
```

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_A -home-node node_A_4-IP -home-port elb -address
172.17.26.11 -netmask 255.255.255.0
[Job 262] Job succeeded: Interface Create is successful.
```

```
cluster_A::> :metrocluster configuration-settings interface create
-cluster-name cluster_A -home-node node_A_4-IP -home-port elb -address
172.17.27.11 -netmask 255.255.255.0
[Job 263] Job succeeded: Interface Create is successful.
```

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_B -home-node node_B_3-IP -home-port elb -address
172.17.26.12 -netmask 255.255.255.0
[Job 264] Job succeeded: Interface Create is successful.
```

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_B -home-node node_B_3-IP -home-port elb -address
172.17.27.12 -netmask 255.255.255.0
[Job 265] Job succeeded: Interface Create is successful.
```

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_B -home-node node_B_4-IP -home-port elb -address
172.17.26.13 -netmask 255.255.255.0
[Job 266] Job succeeded: Interface Create is successful.
```

```
cluster_A::> metrocluster configuration-settings interface create
-cluster-name cluster_B -home-node node_B_4-IP -home-port elb -address
172.17.27.13 -netmask 255.255.255.0
[Job 267] Job succeeded: Interface Create is successful.
```

6. Verify the MetroCluster IP interfaces are created: metrocluster configuration-settings interface show

```

cluster_A::>metrocluster configuration-settings interface show

DR
Config
Group Cluster Node      Network Address Netmask      Gateway
State
-----
-----
2      cluster_A
      node_A_3-IP
      Home Port: e1a
      172.17.26.10      255.255.255.0      -
completed
      Home Port: e1b
      172.17.27.10      255.255.255.0      -
completed
      node_A_4-IP
      Home Port: e1a
      172.17.26.11      255.255.255.0      -
completed
      Home Port: e1b
      172.17.27.11      255.255.255.0      -
completed
      cluster_B
      node_B_3-IP
      Home Port: e1a
      172.17.26.13      255.255.255.0      -
completed
      Home Port: e1b
      172.17.27.13      255.255.255.0      -
completed
      node_B_3-IP
      Home Port: e1a
      172.17.26.12      255.255.255.0      -
completed
      Home Port: e1b
      172.17.27.12      255.255.255.0      -
completed
8 entries were displayed.

cluster_A>

```

7. Connect the MetroCluster IP interfaces: metrocluster configuration-settings connection connect



This command might take several minutes to complete.

```
cluster_A::> metrocluster configuration-settings connection connect
cluster_A::>
```

8. Verify the connections are properly established: metrocluster configuration-settings connection show

```
cluster_A::> metrocluster configuration-settings connection show
```

DR Group	Cluster Config	Node State	Source Network Address	Destination Network Address	Partner Type
2	cluster_A	node_A_3-IP**	Home Port: e1a 172.17.26.10	172.17.26.11	HA Partner
		completed	Home Port: e1a 172.17.26.10	172.17.26.12	DR Partner
		completed	Home Port: e1a 172.17.26.10	172.17.26.13	DR Auxiliary
		completed	Home Port: e1b 172.17.27.10	172.17.27.11	HA Partner
		completed	Home Port: e1b 172.17.27.10	172.17.27.12	DR Partner
		completed	Home Port: e1b 172.17.27.10	172.17.27.13	DR Auxiliary
		node_A_4-IP	Home Port: e1a 172.17.26.11	172.17.26.10	HA Partner
		completed	Home Port: e1a 172.17.26.11	172.17.26.13	DR Partner
		completed	Home Port: e1a		

```

172.17.26.11      172.17.26.12      DR Auxiliary
completed
      Home Port: e1b
      172.17.27.11      172.17.27.10      HA Partner
completed
      Home Port: e1b
      172.17.27.11      172.17.27.13      DR Partner
completed
      Home Port: e1b
      172.17.27.11      172.17.27.12      DR Auxiliary
completed

DR
Group Cluster Node      Source      Destination
Config State      Network Address      Network Address      Partner Type
-----
2      cluster_B
      node_B_4-IP
      Home Port: e1a
      172.17.26.13      172.17.26.12      HA Partner
completed
      Home Port: e1a
      172.17.26.13      172.17.26.11      DR Partner
completed
      Home Port: e1a
      172.17.26.13      172.17.26.10      DR Auxiliary
completed
      Home Port: e1b
      172.17.27.13      172.17.27.12      HA Partner
completed
      Home Port: e1b
      172.17.27.13      172.17.27.11      DR Partner
completed
      Home Port: e1b
      172.17.27.13      172.17.27.10      DR Auxiliary
completed
      node_B_3-IP
      Home Port: e1a
      172.17.26.12      172.17.26.13      HA Partner
completed
      Home Port: e1a
      172.17.26.12      172.17.26.10      DR Partner
completed
      Home Port: e1a
      172.17.26.12      172.17.26.11      DR Auxiliary

```

```
completed
      Home Port: elb
      172.17.27.12    172.17.27.13    HA Partner
completed
      Home Port: elb
      172.17.27.12    172.17.27.10    DR Partner
completed
      Home Port: elb
      172.17.27.12    172.17.27.11    DR Auxiliary
completed
24 entries were displayed.

cluster_A::>
```

9. Verify disk autoassignment and partitioning: `disk show -pool Pool1`

```

cluster_A::> disk show -pool Pool1
          Usable          Disk      Container      Container
Disk      Size Shelf Bay Type      Type      Name
Owner
-----
-----
1.10.4          -      10   4 SAS      remote    -
node_B_2
1.10.13         -      10  13 SAS      remote    -
node_B_2
1.10.14         -      10  14 SAS      remote    -
node_B_1
1.10.15         -      10  15 SAS      remote    -
node_B_1
1.10.16         -      10  16 SAS      remote    -
node_B_1
1.10.18         -      10  18 SAS      remote    -
node_B_2
...
2.20.0      546.9GB      20   0 SAS      aggregate aggr0_rha1_a1
node_a_1
2.20.3      546.9GB      20   3 SAS      aggregate aggr0_rha1_a2
node_a_2
2.20.5      546.9GB      20   5 SAS      aggregate rha1_a1_aggr1
node_a_1
2.20.6      546.9GB      20   6 SAS      aggregate rha1_a1_aggr1
node_a_1
2.20.7      546.9GB      20   7 SAS      aggregate rha1_a2_aggr1
node_a_2
2.20.10     546.9GB      20  10 SAS      aggregate rha1_a1_aggr1
node_a_1
...
43 entries were displayed.

cluster_A::>

```

10. Mirror the root aggregates: `storage aggregate mirror -aggregate aggr0_node_A_3-IP`



You must complete this step on each MetroCluster IP node.



```

cluster_A::> aggr mirror -aggregate aggr0_node_A_3-IP

Info: Disks would be added to aggregate "aggr0_node_A_3-IP" on node
"node_A_3-IP"
    in the following manner:

    Second Plex

        RAID Group rg0, 3 disks (block checksum, raid_dp)

Physical                                                    Usable
Size      Position   Disk                Type                Size
-----
-----
-          dparity    4.20.0              SAS                  -
-          parity     4.20.3              SAS                  -
-          data      4.20.1              SAS                  546.9GB
558.9GB

Aggregate capacity available for volume use would be 467.6GB.

Do you want to continue? {y|n}: y

cluster_A::>

```

11. Verify that the root aggregates are mirrored: storage aggregate show

```

cluster_A::> aggr show

Aggregate      Size Available Used% State  #Vols  Nodes      RAID
Status
-----
-----
aggr0_node_A_1-FC
    349.0GB    16.84GB   95% online    1 node_A_1-FC
raid_dp,
mirrored,
normal
aggr0_node_A_2-FC
    349.0GB    16.84GB   95% online    1 node_A_2-FC
-----
-----

```

```

raid_dp,

mirrored,

normal
aggr0_node_A_3-IP
      467.6GB    22.63GB    95% online      1 node_A_3-IP
raid_dp,

mirrored,

normal
aggr0_node_A_4-IP
      467.6GB    22.62GB    95% online      1 node_A_4-IP
raid_dp,

mirrored,

normal
aggr_data_a1
      1.02TB     1.01TB     1% online       1 node_A_1-FC
raid_dp,

mirrored,

normal
aggr_data_a2
      1.02TB     1.01TB     1% online       1 node_A_2-FC
raid_dp,

mirrored,

```

## Finalizing the addition of the MetroCluster IP nodes

You must incorporate the new DR group into the MetroCluster configuration and create mirrored data aggregates on the new nodes.

1. Create mirrored data aggregates on each of the new MetroCluster nodes: `storage aggregate create -aggregate aggregate-name -node node-name -diskcount no-of-disks -mirror true`



You must create at least one mirrored data aggregate per site. It is recommended to have two mirrored data aggregates per site on MetroCluster IP nodes to host the MDV volumes, however a single aggregate per site is supported (but not recommended). It is support that one site of the MetroCluster has a single mirrored data aggregate and the other site has more than one mirrored data aggregate.

The following example shows the creation of an aggregate on node\_A\_1-new.

```
cluster_A::> storage aggregate create -aggregate data_a3 -node node_A_1-  
new -diskcount 10 -mirror t
```

Info: The layout for aggregate "data\_a3" on node "node\_A\_1-new" would be:

First Plex

RAID Group rg0, 5 disks (block checksum, raid\_dp)

Physical Size	Position	Disk	Type	Usable Size
-	dparity	5.10.15	SAS	-
-	parity	5.10.16	SAS	-
547.1GB	data	5.10.17	SAS	546.9GB
558.9GB	data	5.10.18	SAS	546.9GB
558.9GB	data	5.10.19	SAS	546.9GB

Second Plex

RAID Group rg0, 5 disks (block checksum, raid\_dp)

Physical Size	Position	Disk	Type	Usable Size
-	dparity	4.20.17	SAS	-
-	parity	4.20.14	SAS	-
547.1GB	data	4.20.18	SAS	546.9GB
547.1GB	data	4.20.19	SAS	546.9GB
	data	4.20.16	SAS	546.9GB

```
547.1GB
```

```
Aggregate capacity available for volume use would be 1.37TB.
```

```
Do you want to continue? {y|n}: y
```

```
[Job 440] Job succeeded: DONE
```

```
cluster_A::>
```

## 2. Configure the MetroCluster to implement the changes: metrocluster configure

```
cluster_A::*> metrocluster configure
```

```
[Job 439] Job succeeded: Configure is successful.
```

```
cluster_A::*>
```

## 3. Verify that the nodes are added to their DR group: metrocluster node show

```
cluster_A::*> metrocluster node show
```

DR Group	Cluster	Node	Configuration State	DR Mirroring	Mode
1	cluster_A	node-A-1-FC	configured	enabled	normal
		node-A-2-FC	configured	enabled	normal
	Cluster-B	node-B-1-FC	configured	enabled	normal
		node-B-2-FC	configured	enabled	normal
2	cluster_A	node-A-3-IP	configured	enabled	normal
		node-A-4-IP	configured	enabled	normal
	Cluster-B	node-B-3-IP	configured	enabled	normal
		node-B-4-IP	configured	enabled	normal

8 entries were displayed.

```
cluster_A::*>
```

## 4. Move the MDV\_CRS volumes from the old nodes to the new nodes in advanced privilege.

- Display the volumes to identify the MDV volumes:



If you have a single mirrored data aggregate per site then move both the MDV volumes to this single aggregate. If you have two or more mirrored data aggregates, then move each MDV volume to a different aggregate.

The following example shows the MDV volumes in the volume show output:

```
cluster_A::> volume show
Vserver      Volume                Aggregate      State      Type      Size
Available  Used%
-----
...

cluster_A    MDV_CRS_2c78e009ff5611e9b0f300a0985ef8c4_A
              aggr_b1              -           RW          -
-           -
cluster_A    MDV_CRS_2c78e009ff5611e9b0f300a0985ef8c4_B
              aggr_b2              -           RW          -
-           -
cluster_A    MDV_CRS_d6b0b313ff5611e9837100a098544e51_A
              aggr_a1              online      RW          10GB
9.50GB      0%
cluster_A    MDV_CRS_d6b0b313ff5611e9837100a098544e51_B
              aggr_a2              online      RW          10GB
9.50GB      0%
...
11 entries were displayed.mple
```

- b. Set the advanced privilege level: `set -privilege advanced`
- c. Move the MDV volumes, one at a time: `volume move start -volume mdv-volume -destination-aggregate aggr-on-new-node -vserver vserver-name`

The following example shows the command and output for moving MDV\_CRS\_d6b0b313ff5611e9837100a098544e51\_A to aggregate data\_a3 on node\_A\_3.

```

cluster_A::> vol move start -volume
MDV_CRS_d6b0b313ff5611e9837100a098544e51_A -destination-aggregate
data_a3 -vserver cluster_A

Warning: You are about to modify the system volume
        "MDV_CRS_d6b0b313ff5611e9837100a098544e51_A". This might
cause severe
        performance or stability problems. Do not proceed unless
directed to
        do so by support. Do you want to proceed? {y|n}: y
[Job 494] Job is queued: Move
"MDV_CRS_d6b0b313ff5611e9837100a098544e51_A" in Vserver "cluster_A"
to aggregate "data_a3". Use the "volume move show -vserver cluster_A
-volume MDV_CRS_d6b0b313ff5611e9837100a098544e51_A" command to view
the status of this operation.

```

- d. Use the volume show command to check that the MDV volume has been successfully moved: `volume show mdv-name`

The following output shows that the MDV volume has been successfully moved.

```

cluster_A::> vol show MDV_CRS_d6b0b313ff5611e9837100a098544e51_B
Vserver      Volume      Aggregate    State      Type      Size
Available Used%
-----
-----
cluster_A    MDV_CRS_d6b0b313ff5611e9837100a098544e51_B
              aggr_a2      online      RW         10GB
9.50GB      0%

```

- e. Return to admin mode: `set -privilege admin`

## Moving the data to the new drive shelves

During the transition, you move data from the drive shelves in the MetroCluster FC configuration to the new MetroCluster IP configuration.

1. To resume automatic support case generation, send an Autosupport message to indicate that the maintenance is complete.
  - a. Issue the following command: `system node autosupport invoke -node * -type all -message MAINT=end`
  - b. Repeat the command on the partner cluster.
2. Move the data volumes to aggregates on the new controllers, one volume at a time.

Use the following section of the *Controller Upgrade Express Guide*.

#### [Creating an aggregate and moving volumes to the new nodes](#)

3. Create SAN LIFs on the recently added nodes.

Use the following section of the *Cluster Expansion Express Guide*.

#### [Updating LUN paths for the new nodes](#)

4. Check if there are any node locked licenses on the FC nodes, if there are, they need to be added to the newly added nodes.

Use the following section of the *Cluster Expansion Express Guide*.

#### [Adding node-locked licenses](#)

5. Migrate the data LIFs.

Use the following section of the *Controller Upgrade Express Guide* but do **not** perform the last two steps to migrate cluster management LIFs.

#### [Moving non-SAN data LIFs and cluster management LIFs to the new nodes](#)

## Removing the MetroCluster FC controllers

You must perform clean-up tasks and remove the old controller modules from the MetroCluster configuration.

1. To prevent automatic support case generation, send an Autosupport message to indicate maintenance is underway.
  - a. Issue the following command: `system node autosupport invoke -node * -type all -message MAINT=maintenance-window-in-hours`  
  
maintenance-window-in-hours specifies the length of the maintenance window, with a maximum of 72 hours. If the maintenance is completed before the time has elapsed, you can invoke an AutoSupport message indicating the end of the maintenance period:`system node autosupport invoke -node * -type all -message MAINT=end`
  - b. Repeat the command on the partner cluster.
2. Identify the aggregates hosted on the MetroCluster FC configuration that need to be deleted.

In this example the following data aggregates are hosted by the MetroCluster FC cluster\_B and need to be deleted: aggr\_data\_a1 and aggr\_data\_a2.



You need to perform the steps to identify, offline and delete the data aggregates on both the clusters. The example is for one cluster only.

```
cluster_B::> aggr show
```

Aggregate	Size	Available	Used%	State	#Vols	Nodes	RAID
-----------	------	-----------	-------	-------	-------	-------	------

Status

```
-----  
-----  
aggr0_node_A_1-FC  
      349.0GB   16.83GB   95% online      1 node_A_1-FC  
raid_dp,  
  
mirrored,  
  
normal  
aggr0_node_A_2-FC  
      349.0GB   16.83GB   95% online      1 node_A_2-FC  
raid_dp,  
  
mirrored,  
  
normal  
aggr0_node_A_3-IP  
      467.6GB   22.63GB   95% online      1 node_A_3-IP  
raid_dp,  
  
mirrored,  
  
normal  
aggr0_node_A_3-IP  
      467.6GB   22.62GB   95% online      1 node_A_4-IP  
raid_dp,  
  
mirrored,  
  
normal  
aggr_data_a1  
      1.02TB    1.02TB    0% online      0 node_A_1-FC  
raid_dp,  
  
mirrored,  
  
normal  
aggr_data_a2  
      1.02TB    1.02TB    0% online      0 node_A_2-FC  
raid_dp,  
  
mirrored,  
  
normal  
aggr_data_a3
```



```

1.37TB    1.35TB    1% online    3 node_A_3-IP
raid_dp,

mirrored,

normal
aggr_data_a4
1.25TB    1.24TB    1% online    2 node_A_4-IP
raid_dp,

mirrored,

normal
8 entries were displayed.

```

```
cluster_B::>
```

3. Check if the data aggregates on the FC nodes have any MDV\_aud volumes, and delete them prior to deleting the aggregates.

You must delete the MDV\_aud volumes as they cannot be moved.

4. Take each of the aggregates offline, and then delete them:

- a. Take the aggregate offline: `storage aggregate offline -aggregate aggregate-name`

The following example shows the aggregate `node_B_1_aggr0` being taken offline:

```

cluster_B::> storage aggregate offline -aggregate node_B_1_aggr0

Aggregate offline successful on aggregate: node_B_1_aggr0

```

- b. Delete the aggregate: `storage aggregate delete -aggregate aggregate-name`

You can destroy the plex when prompted.

The following example shows the aggregate `node_B_1_aggr0` being deleted.

```

cluster_B::> storage aggregate delete -aggregate node_B_1_aggr0
Warning: Are you sure you want to destroy aggregate "node_B_1_aggr0"?
{y|n}: y
[Job 123] Job succeeded: DONE

cluster_B::>

```

5. Identify the MetroCluster FC DR group that need to be removed.

In the following example the MetroCluster FC nodes are in DR Group '1', and this is the DR group that need to be removed.

```
cluster_B::> metrocluster node show
```

DR Group	Cluster Node	Configuration State	DR Mirroring Mode
1	cluster_A		
	node_A_1-FC	configured	enabled normal
	node_A_2-FC	configured	enabled normal
	cluster_B		
	node_B_1-FC	configured	enabled normal
	node_B_2-FC	configured	enabled normal
2	cluster_A		
	node_A_3-IP	configured	enabled normal
	node_A_4-IP	configured	enabled normal
	cluster_B		
	node_B_3-IP	configured	enabled normal
	node_B_3-IP	configured	enabled normal

8 entries were displayed.

```
cluster_B::>
```

6. Move the cluster management LIF from a MetroCluster FC node to a MetroCluster IP node:

```
cluster_B::> network interface migrate -vserver svm-name -lif cluster_mgmt  
-destination-node node-in-metrocluster-ip-dr-group -destination-port  
available-port
```

7. Change the home node and home port of the cluster management LIF: `cluster_B::> network interface modify -vserver svm-name -lif cluster_mgmt -service-policy default-management -home-node node-in-metrocluster-ip-dr-group -home-port lif-port`

8. Move epsilon from a MetroCluster FC node to a MetroCluster IP node:

a. Identify which node currently has epsilon: `cluster show -fields epsilon`

```
cluster_B::> cluster show -fields epsilon
```

node	epsilon
node_A_1-FC	true
node_A_2-FC	false
node_A_1-IP	false
node_A_2-IP	false

4 entries were displayed.

- b. Set epsilon to false on the MetroCluster FC node (node\_A\_1-FC): `cluster modify -node fc-node -epsilon false`
- c. Set epsilon to true on the MetroCluster IP node (node\_A\_1-IP): `cluster modify -node ip-node -epsilon true`
- d. Verify that epsilon has moved to the correct node: `cluster show -fields epsilon`

```
cluster_B::> cluster show -fields epsilon
node           epsilon
-----
node_A_1-FC    false
node_A_2-FC    false
node_A_1-IP    true
node_A_2-IP    false
4 entries were displayed.
```

9. On each cluster, remove the DR group containing the old nodes from the MetroCluster FC configuration.

You must perform this step on both clusters, one at a time.

```
cluster_B::> metrocluster remove-dr-group -dr-group-id 1
```

Warning: Nodes in the DR group that are removed from the MetroCluster configuration will lose their disaster recovery protection.

Local nodes "node\_A\_1-FC, node\_A\_2-FC" will be removed from the MetroCluster configuration. You must repeat the operation on the partner cluster "cluster\_B" to remove the remote nodes in the DR group.

Do you want to continue? {y|n}: y

Info: The following preparation steps must be completed on the local and partner clusters before removing a DR group.

1. Move all data volumes to another DR group.
2. Move all MDV\_CRS metadata volumes to another DR group.
3. Delete all MDV\_aud metadata volumes that may exist in the DR group to be removed.
4. Delete all data aggregates in the DR group to be removed. Root aggregates are not deleted.
5. Migrate all data LIFs to home nodes in another DR group.
6. Migrate the cluster management LIF to a home node in another DR group. Node management and inter-cluster LIFs are not migrated.
7. Transfer epsilon to a node in another DR group.

The command is vetoed if the preparation steps are not completed on the local and partner clusters.

Do you want to continue? {y|n}: y

[Job 513] Job succeeded: Remove DR Group is successful.

```
cluster_B::>
```

## 10. Verify that the nodes are ready to be removed from the clusters.

You must perform this step on both clusters.



At this point, the `metrocluster node show` command only shows the local MetroCluster FC nodes and no longer shows the nodes that are part of the partner cluster.

```
cluster_B::> metrocluster node show
```

```
DR
Group Cluster Node Configuration State DR
-----
-----
-----
1 cluster_A
  node_A_1-FC ready to configure - -
  node_A_2-FC ready to configure - -
2 cluster_A
  node_A_3-IP configured enabled normal
  node_A_4-IP configured enabled normal
  cluster_B
  node_B_3-IP configured enabled normal
  node_B_4-IP configured enabled normal
6 entries were displayed.

cluster_B::>
```

11. Disable storage failover for the MetroCluster FC nodes.

You must perform this step on each node.

```
cluster_A::> storage failover modify -node node_A_1-FC -enabled false
cluster_A::> storage failover modify -node node_A_2-FC -enabled false
cluster_A::>
```

12. Unjoin the MetroCluster FC nodes from the clusters: `cluster unjoin -node node-name`

You must perform this step on each node.

```

cluster_A::> cluster unjoin -node node_A_1-FC

Warning: This command will remove node "node_A_1-FC" from the cluster.
You must
    remove the failover partner as well. After the node is removed,
erase
    its configuration and initialize all disks by using the "Clean
configuration and initialize all disks (4)" option from the
boot menu.
Do you want to continue? {y|n}: y
[Job 553] Job is queued: Cluster remove-node of Node:node_A_1-FC with
UUID:6c87de7e-ff54-11e9-8371
[Job 553] Checking prerequisites
[Job 553] Cleaning cluster database
[Job 553] Job succeeded: Node remove succeeded
If applicable, also remove the node's HA partner, and then clean its
configuration and initialize all disks with the boot menu.
Run "debug vreport show" to address remaining aggregate or volume
issues.

cluster_B::>

```

13. Power down the MetroCluster FC controller modules and storage shelves.
14. Disconnect and remove the MetroCluster FC controller modules and storage shelves.

## Completing the transition

To complete the transition you must verify the operation of the new MetroCluster IP configuration.

1. Verify the MetroCluster IP configuration.

You must perform this step on each cluster.

The following example shows the output for cluster\_A.

```

cluster_A::> cluster show
Node                Health  Eligibility  Epsilon
-----
node_A_1-IP         true   true         true
node_A_2-IP         true   true         false
2 entries were displayed.

cluster_A::>

```

The following example shows the output for cluster\_B.

```
cluster_B::> cluster show
Node                Health  Eligibility  Epsilon
-----
node_B_1-IP         true   true         true
node_B_2-IP         true   true         false
2 entries were displayed.

cluster_B::>
```

2. Enable cluster HA and storage failover.

You must perform this step on each cluster.

3. Verify that cluster HA capability is enabled.

```
cluster_A::> cluster ha show
High Availability Configured: true

cluster_A::>

cluster_A::> storage failover show
Node                Partner                Takeover
-----
node_A_1-IP         node_A_2-IP            true   Connected to node_A_2-IP
node_A_2-IP         node_A_1-IP            true   Connected to node_A_1-IP
2 entries were displayed.

cluster_A::>
```

4. Disable MetroCluster transition mode.

- a. Change to the advanced privilege level: `set -privilege advanced`
- b. Disable transition mode: `metrocluster transition disable`
- c. Return to the admin privilege level: `set -privilege admin`

```
cluster_A::*> metrocluster transition disable

cluster_A::*>
```

5. Verify that transition is disabled:metrocluster transition show-mode

You must perform these steps on both clusters.

```
cluster_A::> metrocluster transition show-mode
Transition Mode
-----
not-enabled

cluster_A::>
```

```
cluster_B::> metrocluster transition show-mode
Transition Mode
-----
not-enabled

cluster_B::>
```



## Copyright Information

Copyright © 2021 NetApp, Inc. All rights reserved. Printed in the U.S. No part of this document covered by copyright may be reproduced in any form or by any means-graphic, electronic, or mechanical, including photocopying, recording, taping, or storage in an electronic retrieval system- without prior written permission of the copyright owner.

Software derived from copyrighted NetApp material is subject to the following license and disclaimer:

THIS SOFTWARE IS PROVIDED BY NETAPP "AS IS" AND WITHOUT ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, WHICH ARE HEREBY DISCLAIMED. IN NO EVENT SHALL NETAPP BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

NetApp reserves the right to change any products described herein at any time, and without notice. NetApp assumes no responsibility or liability arising from the use of products described herein, except as expressly agreed to in writing by NetApp. The use or purchase of this product does not convey a license under any patent rights, trademark rights, or any other intellectual property rights of NetApp.

The product described in this manual may be protected by one or more U.S. patents, foreign patents, or pending applications.

RESTRICTED RIGHTS LEGEND: Use, duplication, or disclosure by the government is subject to restrictions as set forth in subparagraph (c)(1)(ii) of the Rights in Technical Data and Computer Software clause at DFARS 252.277-7103 (October 1988) and FAR 52-227-19 (June 1987).

## Trademark Information

NETAPP, the NETAPP logo, and the marks listed at <http://www.netapp.com/TM> are trademarks of NetApp, Inc. Other company and product names may be trademarks of their respective owners.